



## COUNCIL FOR LEATHER EXPORTS

### Pre-Bid Meeting held on 7<sup>th</sup> December 2016 (Wednesday) at CLE Head Office, Chennai.

Tender Notice No. CLE- HO/ASIDE /CFC-M/2016/02 dated 25.11.2016

Name of Work: *Appointment of Contractor for Electrical Installation Work at Common Facility Centre at Melvisharam Vellore District, Tamilnadu.*

S.No	REFERENCE TO THE TENDER DOCUMENTS	SUBJECT	QUERIES	REPLY
1	A1.3.1	HT CABLE	HT cable earthed or Un- earthed	Earthed
2	A 1.3.2	HT cable terminations	Terminations indoor or outdoor	1 No outdoor terminations
3	A 1.3.3	HT cable terminations	Terminations indoor or outdoor	3 Nos. indoor terminations
4	A3	Transformer	IS 2026 or IS 1180	As per New IS 1180 shall be followed
5		Transformer	Additional make Approval	3 makes given in the tender is final
6	A 3.3	BUS duct	Bus duct flexible Copper or aluminum	Copper shall be provided
7	A.V.1	MAIN MV PANEL	500 KVA DG I/C rating 800A 4P EDO ACB provided in SLD, but 500 KVA DG I/C rating 800A 4P MCCB mentioned in BOQ. Kindly confirm which is to be consider.	800A 4P ACB provided
8	A.V.2	APFC PANEL	170A normal contactor provided in the SLD/BOQ. Normally capacitor duty contactor to be provided. Kindly confirm.	Capacitor duty contactor shall be provided as per BOQ
9	A.V.2	APFC PANEL	Reactor not provided in the SLD. As per Boq 7% reactor given. Which to be consider Kindly confirm	7% reactor shall be provided as per BOQ
10	A.V.4	SPP-1	630A TPN MCCB Incomer mentioned in SLD, But 800A TPN MCCB mentioned in BOQ. Which is to be consider Kindly confirm	630A TPN MCCB shall be provided

11	A.V.7	SPP-4	OUTGOING : 1 No 125 A TPN MCCB & 4 Nos 63 A TPN MCCB as per SLD, But 5 Nos 63 A TPN MCCB mentioned in BOQ. Which is to be consider kindly confirm.	5 Nos. outgoing shall be provided as per BOQ
12		LT panel	BOQ and Drawing Bus bar sizes are not matching	0.7A per SQmm shall be considered
13	A.X 1.1 & 1.2	DG set	DG sets in GTP and BOQ are not matching	500 kVA and 250 kVA DG sets shall be provided as per BOQ
14	B.VI.1	10KVA UPS	10KVA UPS 3Phase in / 3Phase out is not available with some of the approved makes - Kindly clarify if we can also use 3Phase in / 1Ph out or 1Ph in / 1Ph	Shall be provided 3phse in / 3 phase out
15	B.VI.2	5 KVA INVERTER	Input supply of 415 V 3 Phase and output of 230 V 3 Phase mentioned in BOQ. whether output 3 Phase or 1 phase Kindly confirm.	Single phase in / single phase out shall be provided
16	B.IV.	LIGHTINING ARRESTORS	Kindly give the additional make approval and cable	3 makes given in the tender is final. Cables recommended for LA shall be provided
17		Sub stations	As per New Rules area required for 17mx 10m	17m x10m is required for Chengalpet MRT. Area given in Drawing meets requirement of other area.
18		FRB cabin	Size Required	5(L) x 4(W) x 6.5 (h) feet
19		EB merting box	Metering BOX supply consumers	Metering box to be provided by TNEB
	<b>Approved makes</b>			
		HT panel	Request to provide make	System control/ megawin/ Excel power
		Telephone works	Request to provide make	Mollex/ Legrand/Beldon
		Net works	Request to provide make	Mollex/ Legrand/Beldon
		CCTV	Request to provide make	Hikivision/ sony/ sumsung
<b>Lighting</b>				
		<b>Bajaj fittings cat No. (Other equivalent approved fittings can also be used)</b>		

	<b>Conventional</b>			
	A.X.1	BTHBX 654		
	A.X.2	BTIR 128		
	A.X.3	BTI 228 PC		
	A.X.4	BMR 218 CFL WEBS		
	A.X.5	BMR 118 CFL WEBS		
	A.X.6	BMLA 01 236 CFL WEB2		
	A.X.7	BJMSD T 03 250 MH IP65 WOB		
	A.X.8	BJMSD T 03 250 MH IP65 WOB		
	A.X.9	BJMSD T 03 70 MH IP65 WOB		
	<b>LED</b>			
	A.X.1	BGHB 150W LED GIV		
	A.X.2	BLTRU 40W WH VIVA I		
	A.X.3	BI PC 40W LED		
	A.X.4	BZRSQL 36W GZ1 WH		
	A.X.5	BZSLH 18W WH		
	A.X.6	BZSLH 24W WH		
	A.X.7	BLRB 18W CWc		
	A.X.8	BLRB 9W CWc		
	A.X.9	BRTFG 90W LED		
	A.X.10	BRTFG 2x90W LED		
	A.X.11	BRTFG 90W LED		

The following issues and clarification were also addressed to the bidders based on the queries raised by the representatives.

1. 75% of Running Account Bills (RA Bills) will be paid within 5 working days on receipt of Original RA Bills approved by the PMC-ILIFO and balance 25% payment will be released subject to scrutiny by Technical Agency-CLRI. 25% balance will be released within 15 days from the date of 75% payment made by CLE.

2. No Extension of Date is considered for Bids Submission. Last date for submission shall be remain stand as 15.12.2016 (Thursday) at 3:00 pm at CLE, HO Chennai only as notified in the NIT dated 25.11.2016.
3. All bidders are advised to make a site visit to understand the site condition and requirement thereof.
4. In Tender Document Volume-1 Section 1- B General Condition of Contract Page No.70, Under Clause : 95.1 **Completion Schedule** should be read as **Five (5) months** instead of Eight (8) months wrongly mentioned.
5. It was agreed to provide Soft Copy of Volume - 5 (Indicative Drawings) only in PDF by PMC for submission of 2<sup>nd</sup> Copy as a part of document to be kept in Cover 1 along with Technical Bids.
6. All the bidders were advised to keep the Earnest Money Deposit (EMD) in the form of Demand Draft only drawn from public sector or scheduled bank. This EMD should be kept in Cover 1 along with Technical Bid Documents. **Therefore keeping the EMD by mistake in Cover 2- Financial Bid shall be a disqualification.**
7. It was also informed to the bidders that there shall be Main Cover in which Cover 1 - Technical Bids along with EMD duly sealed and Cover 2 - Financial Bid original duly sealed shall be submitted before the deadline of 3:00 pm on 15.12.2016 (Thursday) at CLE, HO Chennai duly signed in all pages affixing the seal of the company / firm with authorized signatory.
8. Work Completion Certificate shall be indicate the Project Value of the Completed projects.
9. Financial documents should be submitted pertaining to the Financial Year 2013-14, 2014-15 & 2015-16 along with Income Tax filed documents.
10. Copy of valid Electrical Contractors License should be submitted by the Tenderers.

\*\*\*\*\*